



# Clovis Fire Department

## Standard #1.9

### TEMPORARY STREET SIGNS

Prior to commencing work on any homes beyond the tract models or as soon as base rock is placed on the streets, whichever comes first at all intersections, the developer shall install temporary street name signs to the following specifications:

- The temporary street signs shall be on steel or aluminum backing and can range in thickness from .060 to .125 inches.
- Sign backing material shall be six inches (6") in height.
- The signs shall be reflectorized with black letters on a white background.
- The signs shall include the street name and block number.
- The street name letter size is to be a minimum of four inches (4") tall and the block numbers are to be a minimum of two inches (2") tall.



The developer or the developer's contractor shall obtain the sign pole and mounting brackets from the City of Clovis Public Utilities facility located at 155 N. Sunnyside. If the temporary sign is damaged or removed, the subdivider shall replace it with a new temporary sign within four (4) working days.

The sign fees paid by the development shall cover the initial pole and mounting hardware. The contractor/developer will be required to purchase from the City any additional poles and/or mounting hardware needed to replace those damaged or stolen.

Adhering to this standard will assure proper street signage that is vital for emergency response personnel who may be called to assist an injured construction worker or homeowner prior to the City installing the final street signs.